

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,142-00-00

NENWSW Sec. 27, T 17 S, R 27 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Mumma Well # 2

Operator: Thunderbird Drilling Inc.
Name & Address: P.O. #97
Ellinwood, Kansas
67526

County Lane

Well Total Depth 4308 feet 140.0'

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Thunderbird + Allied Cementing License Number 5131

Address P.O. #97 Ellinwood Kansas 67526

Company to plug at: Hour: 10:00am Day: 22 Month: November Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Maynard Weber

(company name) Thunderbird Drilling Inc (phone) 316-564-2577

were: To use 60/40 poz mix 2% gel 3% cc for cement
Pump down 5 1/2" production casing with 2 sx hulls
10 gel - 50sx cement 10gel - 100sx cement,
Pump 150 sx cement down 8 3/8 surface pipe

Signed Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00 noon Day: 22 Month: November Year: 19 83

ACTUAL PLUGGING REPORT Pump down 5 1/2" production casing with
2 sx hulls - 10gel - 50sx cement - 10gel - 200sx cement
reached 800 psi maximum pressure. Pumped
15 sx cement down 8 5/8" surface pipe &
hit a hard 500 psi. So I think the well
had been squeezed.

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1983
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

DATE 12-28-83

INV. NO. 7228-W

Signed Richard W. Lacey
(TECHNICIAN)