

5-29-88

423

R

To: 1 051060  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,466 -00-00  
C. NE NW, SEC. 26, T. 17 S, R. 27 WE

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656

Operator: Davis Petroleum, Inc.  
Name & Address: Route 1, Box 183-B  
Great Bend, KS 67530

4620 feet from S section line  
3300 feet from E section line

Lease Name Mumma Well # 1

County Lane 128.57

Well Total Depth 3956 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 322

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address Route 1, Box 183-B, Great Bend, KS 67530

Company to plug at: Hour: 10 p.m. Day: 28 Month: 5 Year: 19 88

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2632'  
Anhydrite 2034-68'

- 1st plug at 2060' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,
- 3rd plug at 360' with 40 sx cement,
- 4th plug at 40' with 15 sx cement,
- 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 4:45 a.m. Day: 29 Month: 5 Year: 19 88

- ACTUAL PLUGGING REPORT
- 1st plug at 2060' with 50 sx cement,
  - 2nd plug at 1200' with 80 sx cement,
  - 3rd plug at 360' with 40 sx cement,
  - 4th plug at 40' with 15 sx cement,
  - 5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN - 6 1988

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

Signed Richard M. Lacey (TECHNICIAN)

DATE 6-21-88

INV. NO. 20902

NOTICE OF INTENTION TO DRILL

Expected Spud Date... April 18, 1988

(see rules on reverse side)

API Number 15-101-21,466-00-00

OPERATOR: License # 4656
Name Davis Petroleum, Inc.
Address Route 1, Box 183-B
City/State/Zip Great Bend, KS 67530
Contact Person L. D. Davis
Phone 316-793-3051

C NE NW Sec. 26 Twp. 17 S, Rg. 27
4620
3300
Ft. from South Line of Section
Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 660 feet
County Lane

CONTRACTOR: License # 6039
Name L. D. Drilling, Inc.
Address Route 1, Box 183-B
City/State/Zip Great Bend, KS 67530
Well Drilled For: Oil, Gas, OWWO
Well Class: Infield, Pool Ext, Wildcat
Type Equipment: Mud Rotary, Air Rotary, Cable

Lease Name Mumma Well # 1
Ground surface elevation 2580 (estimate) feet MSL

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Depth to bottom of fresh water 75
Depth to bottom of usable water 1200

Surface pipe by Alternate: 1 2 X
Surface pipe planned to be set 320

Conductor pipe required None
Projected Total Depth 4520 feet

Formation Mississippi

If OWWO: old well info as follows:

Operator
Well Name
Comp Date
Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 4-6-88 Signature of Operator or Agent J. M. Vess Title

For KCC Use:

Conductor Pipe Required
This Authorization Expires 10-6-88 feet; Minimum Surface Pipe Required 200 feet per Alt. X

EFFECTIVE DATE: 4-11-88

Approved By [Signature] 4-6-88

SPUD 5-23-88

8 5/8" 320'

C NE NW Sec. 26 Twp. 17 S, Rg. 27 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth (ft.), Formation, and Cement (feet of). Rows include 1st through 5th plugs and rathole to surface.

(2) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

Vertical list of well parameters: PUSHER, TD, SURFACE PIPE, ANHYDRITE, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @ 2060 FT. WI 50 SX, 2nd PLUG @ 1200 FT. WI 80 SX, 3rd PLUG @ 360 FT. WI 40 SX, 4th PLUG @ 40 FT. WI 15 SX, RAT HOLE CIRCULATED WI 15 SX, MOUSE HOLE CIRCULATED WI SX, WATER WELL PLUGGED WI SX, CEMENT COMPANY Allied 40/40 6/70, TECHNICIAN LK

RECEIVED STATE CORPORATION COMMISSION JUN - 6 1988 CONSERVATION DIVISION Wichita, Kansas