

1060348

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,050 -00-00

SE NW SW, SEC. 26, T 17 S, R 27 W/R  
1650 feet from ~~XXX~~ section line  
W SW Corner of  
4290 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9152

Lease Name Repshire Well # 1-26

Operator: Marexco  
Name & Address: 3025 Quail Street  
Lakewood, CO 80215

County Lane

Well Total Depth 4660 151.15 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 366

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Revlin Drilling, Inc. License Number 5671

Address Box 293, Russell, KS 67665

Company to plug at: Hour: noon Day: 27 Month: September Year: 19 84

Plugging proposal received from Gene Augustine

(company name) Revlin (phone) 913-483-4602

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2060' with 50 sx cement

2nd plug at 1330' with 50 sx cement

3rd plug at 410' with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luttich (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:15 pm Day: 27 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2060' with 50 sx cement, 2nd plug at 1330' with 50

sx cement, 3rd plug at 410' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 01 1984

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 10-5-84

INV. NO. 4064

Signed Paul A. Luttich (TECHNICIAN)

9-27 NOV 13 1984