

1 030557

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,240 -00-00

S/2 SE SW, SEC. 24, T 17 S, R 27 W

330 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Benson 'J' Well # 1

Operator: Slawson, Donald C.

County Lane

Name & Address 200 Douglas Building

Well Total Depth 4541 Mississippi 47.58 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Company License Number 5657

Address 200 Douglas Building, Broadway & Douglas, Wichita, KS 67202

Company to plug at: Hour: 1:00 am Day: 29 Month: October Year: 19 85

Plugging proposal received from Bob Rane

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2528' Anhydrite 1921'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 50' below the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls- plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:00 am Day: 29 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1935' with 50 sx cement, 2nd plug at 1165' with 80 sx

cement, 3rd plug at 470' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

NOV 4 1985

NOV 1 1985

Signed Steve Durrant
(TECHNICIAN)

NO. 10893

CONSERVATION DIVISION
Wichita, KansasFORM CP-2/3
Rev. 01-84