

To: 1 020681
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-12

API NUMBER 15- 101-21,651-00-00
150' SE NW SE, SEC. 23, T. 17 S, R. 27 W&E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5030

1874 feet from S section line
1874 feet from E section line

Operator: Vess Oil Corporation
Name & Address 8100 E. 22nd St. N, Bldg. 300
Wichita, KS 67226

Lease Name Benson-Atwell Well # 1-23
County Lane 147.55
Well Total Depth 4540 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 333

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039
Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: _____ Day: 12 Month: 6 Year: 19 93

Plugging proposal received from Bessie
(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 2000' with 50 sx cement, 2nd plug at 1050' with 80 sx cement,
3rd plug at 360' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6 p.m. Day: 12 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 2000' with 50 sx cement,
2nd plug at 1050' with 80 sx cement,
3rd plug at 360' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel # floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
~~check~~ (did not) observe this plugging.

DATE 6-22-93
INV. NO. 379723

Signed Glenn R Barlow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1993
CONSERVATION DIVISION
KANSAS

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

15-101-21,651-00-00
06/03/93 12:43

FOR KCC USE
EFFECTIVE DATE: 6-8-93
DISTRICT: 1
SEAT: X Yes No

State of Kansas
NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date: June 2 1993
month day year

Spot 150 East XX West
SE NW SE Sec 23 Twp 17 S. Rg 27

OPERATOR: License # 5030
Name: Vess Oil Corporation
Address: 8100 E. 22nd St. N., Bldg. 300
City/State/Zip: Wichita, KS 67226
Contact Person: W. R. Horgan
Phone: 316-682-1537

1874 feet from South North line of Section
1874 feet from East West line of Section
IS SECTION X REGULAR IRREGULAR
(NOTE: Locate well on the Section Plat on Reverse Side)
County: Lane
Lease Name: Benson-Atwell Well # 1-23
Field Name: Wildcat
Is this a Prorated/Spaced Field? yes X no
Target Formation(s): LKC
Nearest lease or unit boundary: 766'
Ground Surface Elevation: 2590' feet MSL
Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 100'
Depth to bottom of usable water: 1200'
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 320
Length of Conductor pipe required: None
Projected Total Depth: 4600'
Formation at Total Depth: Miss
Water Source for Drilling Operations:
... well X farm pond other
DWR Permit #:
Will Cores Be Taken?: yes X no
If yes, proposed zone:

CONTRACTOR: License #: 6039
Name: L. D. Drilling, Inc.

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X Mud Rotary
... Gas ... Storage ... Peel Ext. ... Air Rotary
... OWD ... Disposal X Wildcat ... Cable
... Seismic: ... # of Holes ... Other
... Other

If OWD, old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
if yes, true vertical depth:
Bottom Hole Location:

AFFIDAVIT

Pusher
SPUD DATE 6-3-93 INIT. SM
LENGTH SURFACE PLANNED 320'-85/8"
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 9 3/4 @ 333 CONDUCTOR
ANHYDRITE T- B ELEVATION
TD 4540 FORMATION
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
2015 Anhydrite Base @ 8000 Ft. W/ 80 SX
1/2 Base Anyh. @ 1050 Ft. W/ 80 SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 360 Ft. W/ 40 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond)
Hauling
TECHNICIAN G.B. DATE 6-11-93
TYPE OF CEMENT 60/40 pos 6790 1/4 # Flow
STARTING TIME (AM/PM) DATE
COMPLETION TIME 6 (AM/PM) DATE 6-12
CEMENT COMPANY Allied
RECEIVED
STATE COMMISSION
OBSERVATION DIVISION
Wichita, Kansas
JUNE 17 1993