

1 080267

API NUMBER 15-101-21,078-00-00 *12*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE NW, SEC. 23, T 17 S, R 27 W/E

3300 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Repshire 'A' Well # 2

Operator: Donald C. Slawson

County _____ Lane 149.83

Name & Address 200 Douglas Building.

Well Total Depth 4610 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 338

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drilling, Co., Inc. License Number 5657

Address 200 Douglas Building, Wichita, KS 67202

Company to plug at: Hour: 3:00 am Day: 27 Month: November Year: 19 84

Plugging proposal received from Jimmie Loftis

(company name) Slawson Drilling Co., Inc. (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2020' with 50 sx cement

2nd plug at 1000' with 50 sx cement

3rd plug at 380' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement.

6th plug to circulate rat hole with 10 sx cement
Plugging Proposal Received by J. H. Metz

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:00 am Day: 27 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2020' with 50 sx cement, 2nd plug at 1000' with 50

sx cement, 3rd plug at 380' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement

RECEIVED
STATE CORPORATION COMMISSION

DEC 05 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(if additional description is necessary, use BACK of CONSERVATION DIVISION

Wichita, Kansas

INVOICED

DATE 12-13-84

Signed J. H. Metz (TECHNICIAN) *SD*

INV. NO. 5978