

1 050732

API NUMBER 15- 101-21,266 -00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C E/2 NE, SEC. 36, T 17 S, R 27 W/K
3960 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6420
Operator: KRM Petroleum Corporation
Name & Address: 1900 Grant Street, Suite 300
Denver, CO 80203

Lease Name Thelma Well # 1-36
County Lane 152.10
Well Total Depth 4680 Mississippi feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 338

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor H-30, Inc. License Number 5107
Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 5:00 am Day: 24 Month: December Year: 19 85

Plugging proposal received from Gary Peugh
(company name) H-30 (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2045-2074'
Elevation 2658 GL

- 1st plug at the base of the Anhydrite with 50 sx cement
 - 2nd plug at 1100' with 80 sx cement
 - 3rd plug 50' below the base of the surface pipe with 50 sx cement
solid bridge
 - 4th plug hulls - plug at 40' -- cement to surface with 10 sx cement
 - 6th plug to circulate rat hole with 15 sx cement
- Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7:00 am Day: 24 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2074' with 50 sx cement, 2nd plug at 1100' with 80 sx
cement, 3rd plug at 388' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 06 1986
INV. NO. 11847

JAN 2 1986

Signed Richard W. Lacey
(TECHNICIAN)