

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,849-00-00

NE SE, Sec. 36, T 17 S, R 27 W X

1980 feet from X/S section line

660 feet from X/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5760

Lease Name WHIPPLE Well # 1

Operator: IREX
Name & Address 1670 Broadway #3301
DENVER, CO 80202

County LANE

Well Total Depth 4680 feet #152.10

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 345 w/2500 ft

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 617 Union Center, WICHITA, KS 67202

Company to plug at: Hour: 4:00 AM Day: 20 Month: SEPT. Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO BERNIE MEYERS

(company name) MURFIN (phone)

were: TO USE 60/40 Pozmix, 2% gel, -3% CC & locate
1st plug @ 2040 w/50 sy cement;
2nd plug @ 1500 w/50 sy cement;
3rd plug @ 390 w/40 sy cement;
4th plug @ 40' w/solid bridge & 10 sy cement & circ.
15 sy in rat hole

Signed Robert Barbutan (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:15 AM Day: 20 Month: SEPT Year: 19 83

ACTUAL PLUGGING REPORT PLUGGED AS ORDERED
CEMENTING BY HALLIBURTON

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1983
CONSERVATION DIVISION
Wichita, Kansas

Remarks:

I hereby certify that the above plugging instructions were given as herein stated and that I () / did not) observe this plugging.

INVOICED
DATE 9-28-83
INV. NO. 5544-W

Signed R Barbutan (TECHNICIAN)