

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
290 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-20, 893-00-00

NW/4 Sec. 35, T 17 S, R 27 W 1/4

1650 feet from N 1/4 section line

330 feet from W 1/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name REPSHIRE Well # 1 R

Operator: Chief Drilling Co, Inc  
Name & Address 905 Century Plaza  
Wichita, KS 67202

County LANE

Well Total Depth 4649 feet 151.09

Conductor Pipe: Size          feet         

Surface Casing: Size 8 5/8 feet 322

Abandoned Oil Well          Gas Well          Input Well          SWD Well          D&A X

Other well as hereinafter indicated         

Plugging Contractor Warrior Drilling, Inc License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 8 AM Day: 30 Month: DEC Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO HAROLD DINKLE

(company name) WARRIOR (phone)         

were: to use 60/40 Pozmix, w/2% gel-3% CC AND SPOT THE  
1<sup>ST</sup> plug @ 2050' w/50 sy - 2<sup>ND</sup> plug @ 1500' w/50 sy -  
3<sup>RD</sup> plug @ 900' w/50 sy - 4<sup>TH</sup> plug @ 360' w/40 sy -  
5<sup>TH</sup> plug @ 40' w/solid bridge, plug and 10 sy.  
Circulate 15 sy in the rat hole.

Signed R. Barburton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All          Part          None X

Operations Completed: Hour: 12 Noon Day: 30 Month: DEC Year: 19 83

ACTUAL PLUGGING REPORT plugged as ordered.  
Cementing by Halliburton  
Ticket # 41416

Remarks:           
          
        

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

INVOICED RECEIVED  
STATE CORPORATION COMMISSION  
DATE 1-18-84  
INV. NO. 2030  
JAN 0 2 1984  
CONSERVATION DIVISION  
Wichita, Kansas

Signed R. Barburton  
(TECHNICIAN)