

1 030332

API NUMBER 15-101-21,060-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NW NW SE, SEC. 34, T 17 S, R 27 W/X  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5248

Lease Name Elgin Repshire Well # 2

Operator: Olympic Petroleum Company  
Name & Address 2121 South Columbia Ave.  
Tulsa, OK 74114

County Lane Lane 151.13

Well Total Depth 4650 feet

Conductor Pipe: Size            feet

Surface Casing: Size 8 5/8 feet 301

Abandoned Oil Well            Gas Well            Input Well            SWD Well            D&A X

Other well as hereinafter indicated           

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 1:00 pm Day: 24 Month: November Year: 19 84

Plugging proposal received from Sam Waggoner

(company name) Red Tiger (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2080' with 50 sx cement

2nd plug at 960' with 50 sx cement

3rd plug at 330' with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Steve Dumont  
(TECHNICIAN)

Plugging Operations attended by Agent?: All            Part            None X

Operations Completed: Hour: 2:30 pm Day: 24 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2080' with 50 sx cement, 2nd plug at 960' with 50

sx cement, 3rd plug at 330' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 28 1984

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-4-84

Signed Steve Dumont  
(TECHNICIAN)

5763  
11-24