

1030274

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,030 -00-00

E/2 NE NW, SEC. 34, T 17 S, R 27 W/X
4620 feet from ^N SE Corner of XXV section line
2970 feet from ^W SE Corner of XXV section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Whipple Well # 2

Operator: Chief Drilling Co., Inc.

County Lane

Name & Address 905 Century Plaza

Well Total Depth 4655 151.29 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 336

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Company License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 1:00 am Day: 20 Month: September Year: 1984

Plugging proposal received from Harold Dinkle

(company name) Warrior (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2100' with 50 sx cement

2nd plug at 1150' with 50 sx cement

3rd plug at 390' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Shumant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:30 am Day: 20 Month: September Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement, 2nd plug at 1150' with 50 sx cement, 3rd plug at 390' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SFP 24 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

(xxx / d/d) observe this plugging.

Signed Steve Shumant
(TECHNICIAN)

INVOICED
DATE 9-27-84
INV. NO. 3914