

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-101-20942 -00-00

LEASE NAME Erskin

WELL NUMBER 31-1

SPOT LOCATION SW/SW/NE

SEC. 31 TWP 12S RGE. 27 ~~(E)~~ ~~(W)~~ (W)

COUNTY Lane

DATE WELL COMPLETED 4/5/84

PLUGGING COMMENCED 4/6/84

PLUGGING COMPLETED 4/6/84

TYPE OR PRINT

PLEASE FILL OUT COMPLETELY
 AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR High Summit Oil & Gas, Inc.

ADDRESS 3817 Carson St., Evans, CO 80620

PHONE # (303) 330-7600 OPERATORS LICENSE NO. 9380

CHARACTER OF WELL D&A
 (OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Great Bend

IS ACC-1 FILED? yes IF NOT, IS WELL LOG ATTACHED? yes

PRODUCING FORMATION Cherokee DEPTH TO TOP 4500 BOTTOM 4600 T.D. 4600

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing	possible oil & gas	3962	4295			
Marmonton	" " "	4325	4500			
Cherokee	" " "	4500	4600			

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Equalized 50 sack plug of 60/40 POZ 2% gel, 3% C/C cmt. @ 2040'; equalized 50 sack plug of 60/40 POZ 2% gel 3% C/C cmt @ 1320'; equalized 50 sack plug of 60/40 POZ 2% gel, 3% C/C cmt @ 420'; equalized 25 sack plug of 60/40 POZ 2% gel 3% C/C cmt @ 40'. Circulated to surface. Plugged 8-5/8 csg. stub. Equalized 15 sack plug of 60/40 POZ 2% gel, 3% C/C in rat hole. Equalized 10 sack plug of 60/40 POZ 2% gel 3% C/C in mouse hole.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Sun Oil Well Cementing LICENSE No. _____

ADDRESS PO Box 169

Great Bend, Kansas 67530

STATE OF Colorado COUNTY OF Weld, SS.

Wendall H. Jamison (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Wendall H. Jamison

(ADDRESS) 3817 Carson St. Evans, CO 80620

SUBSCRIBED AND SWORN TO BEFORE ME THIS 10 DAY OF April, 1984

Julie Ann Galagi
 NOTARY PUBLIC

1215 32 St. Evans, CO 80620

MY COMMISSION EXPIRES: February 15, 1988



RECEIVED
 STATE CORPORATION COMMISSION

APR 16 1984

CONSERVATION DIVISION
 Wichita, Kansas

FORM CP-4
 REVISED 06-83