

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,551-00-00

LEASE NAME Gill

WELL NUMBER 2

4290 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 35 TWP. 16 SRGE. 19 ~~XXXX~~(W)

COUNTY Lane

Date Well Completed 06-16-90

Plugging Commenced 06-17-90

Plugging Completed 06-18-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Energy Exploration, Inc.

ADDRESS 1002 S. Broadway, Wichita, KS 67211

PHONE#(316) 267-7336 OPERATORS LICENSE NO. 5063

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 06-16-90 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	209.49	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Filled hole w/heavy mud to 2230'; 1st plug @ 2230 to 2030 w/50 sxs; 2nd plug @ 1250 to 930 w/80 sxs; 3rd plug @ 230 to 70 w/40 sxs; 4th plug @ 40' to surface w/10 sxs; 15 sxs. in rathole.
All cement 60/40 pozmix w/6% gel and 1/4# Floceal per sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, #801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Energy Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main #801, Wichita, KS

DEBORAH K. AMMERMAN
Notary Public - State of Kansas
My Appt. Expires 3-1-92

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 19 90

Deborah K. Ammerman
Notary Public

My Commission Expires: 3-1-92

15-101-21551-00-00

ABERCROMBIE DRILLING, INC.

801 UNION CENTER
WICHITA, KANSAS 67202

Energy Exploration, Inc.
1002 S. Broadway
Wichita, KS 67211

GILL #2
SE NW NE Sec. 35-16S-29W
Lane County, KS

Contractor: Abercrombie Drilling, Inc.
Surface: 8 5/8 @ 209.49 w/140 sxs.

DRILLERS WELL LOG

06-06-90	0 to 135	Clay and Sand
	135 to 214	Shale
06-07-90	214 to 1470	Sand and Shale
06-08-90	1470 to 2420	Sand and Shale
	2420 to 2710	Shale and Lime
06-09-90	2710 to 3125	Shale and Lime
	3125 to 3305	Lime and Shale
06-10-90	3305 to 3645	Shale and Lime
	3645 to 3790	Lime and Shale
06-11-90	3790 to 3975	Lime and Shale
	3975 to 4095	Shale and Lime
	4095 to 4192	Lime and Shale
06-12-90	4192 to 4240	Lime and Shale
06-13-90	4240 to 4267	Shale and Lime
	4267 to 4304	Lime and Shale
06-14-90	4304 to 4340	Shale and Lime
	4340 to 4412	Lime and Shale
06-15-90	4412 to 4445	Shale and Lime
	4445 to 4530	Lime and Shale
06-16-90	4530 to 4588	Lime and Shale
06-17-90	4588 to 4640	Lime and Shale
	4640	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1990
06-26-1990
CONSERVATION DIVISION
Wichita, Kansas