


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

WELL PLUGGING RECORD

15-101-20256-00-00

Lane _____ County. Sec. 35 Twp. 16S Rge. (E) 29 (W)
Location as "NE/CNW/SW" or footage from lines C S/2 SW SE
Lease Owner Chief Drilling Co., Inc.
Lease Name Fred Eaton Well No. #1
Office Address 905 Century Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12/11/77 19_____
Application for plugging filed 12/13/77 19_____
Application for plugging approved 12/13/77 19_____
Plugging commenced 12/11/77 19_____
Plugging completed 12/11/77 19_____
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19_____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4562' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	289'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe @ 300' w/70 sx. 50/50; 6% gel
Plugged through drill pipe @ 240' w/20 sx. " "
Plugged through drill pipe @ 40' w/10 sx. " "

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1977
12-14-1977
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
905 Century Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of December, 19 77

My commission expires _____

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
Marilyn Sinard
Notary Public.

WELL LOG

15-101-20256-00-00

CHIEF DRILLING CO., INC.
905 Century Plaza
Wichita, Kansas 67202

#1 FRED EATON
C S/2 SW SE Sec. 35-16S-29W
Lane County, Kansas

CONTRACTOR: Warrior Drilling, Inc.
CASING RECORD: 8 5/8" @ 289' w/175 sx.

COMMENCED: November 30, 1977
COMPLETED: December 11, 1977

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATIONS</u>
Surface Sand & Shale	0	295	2798 Gr.
Sand & Shale	295	300	2800 D.F.
Shale	300	2199	2803 K.B.
Anhydrite	2200	2230	
Shale	2231	3858	
Shale & Lime	3858	4137	
Lime	4137	4562	
Total Depth	4562		

<u>FORMATION TOPS</u>	
Anhydrite	2200 + 603
Base Anhydrite	2230 + 573
Heebner	3932 - 1129
Lansing	3973 - 1170
BKC	4310 - 1507
Marmaton	4330 - 1527
Ft. Scott	4478 - 1675
Cherokee Shale	4508 - 1705
B/Cher. Lime	4554 - 1751
RTD	4562 - 1759

D & A

RECEIVED
STATE CORPORATION COMMISSION

DEC 14 1977
12-14-1977
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C S/2 SW SE Sec. 35-16S-29W, Lane County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Vice-President.

Subscribed and sworn to before me this 13th day of December, 1977.

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
Marilyn Sinard Notary Public