


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Lane \_\_\_\_\_ County. Sec. 35 Twp. 16S Rge. (E) 29 (W) \_\_\_\_\_  
Location as "NE/CNW/SW" or footage from lines NE NW SW  
Lease Owner Chief Drilling Co., Inc.  
Lease Name Eaton #A Well No. #2  
Office Address 905 Century Plaza, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 28, 1978 19\_\_\_\_  
Application for plugging filed March 28, 1978 19\_\_\_\_  
Application for plugging approved March 28, 1978 19\_\_\_\_  
Plugging commenced March 28, 1978 19\_\_\_\_  
Plugging completed March 28, 1978 19\_\_\_\_  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4565 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	288'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged through drill pipe @ 800' w/70 sx. cement  
Plugged through drill pipe @ 240' w/20 sx. cement  
Plugged through drill pipe @ 40' w/10 sx. cement

RECEIVED  
STATE CORPORATION COMMISSION

APR 03 1978  
04-03-1978  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Chief Drilling Co., Inc.  
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson  
905 Century Plaza, Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of March, 19 78

Marilyn Sinard  
Marilyn Sinard Notary Public.

My commission expires \_\_\_\_\_

MARILYN SINARD  
STATE NOTARY PUBLIC  
SEDGWICK COUNTY, KANSAS  
MY COMM. EXP. APR. 30, 1979

WELL LOG

15-101-20302-00-00

CHIEF DRILLING CO., INC.  
905 Century Plaza  
Wichita, Kansas 67202

#2 EATON "A"  
NE NW SW Sec. 35-16S-29W  
Lane County, Kansas

CONTRACTOR: Warrior Drilling, Inc.  
CASING RECORD: 8 5/8" @ 288' w/180 sx.

COMMENCED: March 20, 1978  
COMPLETED: March 28, 1978

FORMATION	FROM	TO	ELEVATIONS
Surface Sand & Shale	0	292	2801 Gr.
Sand & Shale	292	1530	2803 D.F.
Shale	1530	4066	2806 K.B.
Shale & Lime	4066	4172	
Lime	4172	4565	
RTD	4565		

FORMATION TOPS	
Anhydrite	2214 + 592
Base Anhydrite	2243 + 563
Heebner	3943 - 1137
Lansing	3979 - 1173
BKC	4323 - 1517
Marmaton	4330 - 1524
Ft. Scott	4482 - 1676
RTD	4565 - 1759

D & A

RECEIVED  
STATE CORPORATION COMMISSION

APR 03 1978  
04-03-1978  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C NE NW SW Sec. 35-16S-29W,  
Lane County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*Jim Robinson*  
Jim Robinson, Vice-President

Subscribed and sworn to before me this 31st day of March, 1978.

MARILYN SINARD  
STATE NOTARY PUBLIC  
SEDGWICK COUNTY, KANSAS  
MY COMM. EXP. APR. 30, 1979

*Marilyn Sinard*  
Marilyn Sinard Notary Public