

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-00417-00-00
Spot: SWSWSWNW Sec/Twnshp/Rge: 10-35S-34W
2493 feet from N Section Line, 245 feet from W Section Line
Lease Name: GROVER Well #: 1
County: SEWARD Total Vertical Depth: 2746 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: PO BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2098		WITH 25 SX CMT
SURF	10.75	718		WITH 275 SX CMT
L1	5.5	2619		SLOTTED LINER 2619-2746
PROD 7		2634	1096	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/02/2012 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 2584' WITH 10 SX CMT. PLUG AT 1630' WITH 80 SX CMT. PLUG AT 750' WITH 100 SX CMT. FILL FROM 60' TO SURFACE.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2012 1:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

TBG STUCK IN HOLE, SHOT TBG @ 2488'. PULLED 10' & TBG STUCK. PUMPED 10 BBL FLUID DOWN TBG. STILL UNABLE TO MOVE. RE-SHOT TBG @ 2130' & PULLED OUT OF HOLE WITH TBG. SET CIBP @ 2098' WITH 25 SX CMT. SHOT 7" CASING @ 1600', UNABLE TO PULL, RE-SHOT 7" @ 1096'. POOH WITH CASING. RIH W/TBG TO 1630' & PUMPED 80 SX CMT. PUMP 100 SX CMT AT 750'. PUMP 25 SX CMT AT 60'.

Perfs:

Top	Bot	Thru	Comments
2634	2740		CHASE

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
MAR 12 2012
KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED

MAR 28 2012

KCC WICHITA

Form CP-2/3

3/29/12

AMW