

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20572-00-01
Spot: NESWSE Sec/Twnshp/Rge: 16-29S-32W
1292 feet from S Section Line, 1456 feet from E Section Line
Lease Name: SIMMONS Well #: 2X-16
County: HASKELL Total Vertical Depth: 5488 feet

Operator License No.: 33136
Op Name: ANADARKO E & P COMPANY LP
Address: PO BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2593		WITH 10 SX CMT
SURF	8.625	782		WITH 300 SX CMT
PROD	5.5	3286	0	WITH 660 SX CMT

Well Type: SWD UIC Docket No: D26403.0 Date/Time to Plug: 03/06/2012 9:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 2600' WITH 2 SX CMT. PLUG AT 1850' WITH 30 SX CMT. FILL 5 1/2" FROM 810' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/06/2012 1:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 2593' WITH 10 SX CMT. 1ST PLUG POOH W/TBG TO 1850' & PUMP 25 SX MUD & 50 SX CMT. 2ND PLUG POOH TO 830' & FILL 5 1/2" CASING WITH 100 SX CMT. TIE ONTO THE 5 1/2" X 8 5/8" ANNULAR & PUMP 15 SX CMT. PRESSURE TO 350 PSI.

Perfs:

Top	Bot	Thru	Comments
3140	3150		COUNCIL GROVE
2672	2762		CHASE

Remarks: **COMPLIANCE ISSUE: MIT LTR SENT** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Jack MacLaskey
(TECHNICIAN)

RECEIVED
MAR 12 2012
KCC DODGE CITY

RECEIVED Form CP-2/3
MAR 28 2012 3/29/12
KCC WICHITA