

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21354-00-00
Spot: NENWNWSE Sec/Twnshp/Rge: 5-28S-17W
2329 feet from S Section Line, 2286 feet from E Section Line
Lease Name: RICHARDSON Well #: 1-A
County: KIOWA Total Vertical Depth: 4840 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	431		WITH 280 SX CMT
PROD	4.5	4839	2155	WITH 225 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/20/2012 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JIM BYERS / KEVIN FISCHER Company: APOLLO ENERGIES Phone: (620) 672-9001

Proposed Plugging Method: SET CIBP @ 4715' WITH 2 SX CMT. PLUG AT 1050' WITH 15 SX GEL & 50 SX CMT. PLUG AT 460' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/20/2012 11:15 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 4712' WITH 5 SX CMT. 1ST PLUG AT 1047' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 478' WITH 50 SX CMT. 3RD PLUG AT 41' WITH 25 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4765	4773		KINDERHOOK SA

RECEIVED
MAR 28 2012

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL 200# HULLS BY QUALITY WELL SERVICE. KCC WICHITA

Plugged through: CSG

District: 01

Signed: Eric MacLaren
(TECHNICIAN)

RECEIVED
MAR 21 2012
KCC DODGE CITY

3/29/12 Form CP-2/3

19024