

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22830-00-00
Spot: NWNESW Sec/Twnshp/Rge: 3-16S-25W
2310 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HAROLD Well #: 3
County: NESS Total Vertical Depth: 4531 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 341 | | WITH 225 SX CMT |
| DVT | | 1951 | | WITH 500 SX CMT |
| PROD | 4.5 | 4524 | 0 | WITH 175 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2012 1:00 PM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: CURT Company: BEREXCO LLC Phone: (316) 265-3311

Proposed Plugging Method: RUN TBG TO TOP OF FISH TO 3400'. SPOT 10 SX GEL W/200# HULLS MIXED IN & 40 SX CMT. PERFORATE AT 800'. PULL TBG TO 1950' & SPOT 30 SX CMT. PULL TBG TO 800' & CIRCULATE ANNULUS WITH CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 03/14/2012 5:55 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

TBG FISH @ 2645'. RAN TBG TO 2645' & PUMP 10 SX GEL W/200# HULLS & 40 SX CMT. PERFORATED 4 1/2" @ 800'. PULLED TBG TO 1950' & PUMPED 30 SX CMT. PULLED TBG TO 800' & PUMPED 60 SX CMT CIRCULATING CMT TO SURFACE UP 4 1/2". SHUT IN 4 1/2". PUMPED 50 SX CMT INTO PERFS PRESSURED TO 400 PSIG. PULLED TBG OUT & TOPPED OFF WITH 10 SX CMT. PRESSURED 8 5/8" X 4 1/2" ANNULUS TO 500 PSIG WITH 20 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|-----------|
| 4524 | 4531 | | OPEN HOLE |
| 4426 | 4429 | | FT SCOTT |

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

RECEIVED
MAR 28 2012

KCC WICHITA

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
MAR 22 2012
KCC DODGE CITY

✓ 3/29/12