

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-02008-00-00
Spot: NESENE Sec/Twnshp/Rge: 16-19S-20W
3630 feet from S Section Line, 330 feet from E Section Line
Lease Name: WEBS C Well #: 3
County: RUSH Total Vertical Depth: 4300 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1500		WITH 2 SX CMT
SURF	8.625	190		WITH 175 SX CMT
PROD	5.5	4298	0	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/12/2012 9:30 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (316) 265-3311

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 03/12/2012 2:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

SQUEEZED AT 674' - 689' WITH 240 SX CMT. 3/11/12: LOCKSET PACKER @ 4136' WITH 2 SX CMT. SET CIBP @ 1500' WITH 2 SX CMT. CMT BOND LOG SHOWED GOOD CEMENT BOND FROM 1200' TO 280'. 3/12/12: RUN TBG IN TO TAG CIBP @ 1500'. PULLED TBG TO 1495' & PUMPED 130 SX CMT CIRCULATING CMT TO THE SURFACE. PULLED TBG OUT OF HOLE & TOPPED OFF WITH 15 SX CMT. PUMPED 50 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
4207	4212		

Remarks: USED 60/40 POZMIX 4% GEL 400# HULLS BY QUALITY WELL SERVICE.

Plugged through: TBG

RECEIVED

MAR 28 2012

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

KCC WICHITA

RECEIVED
MAR 21 2012
KCC DODGE CITY

Form CP-2/3

3/29/12

ROWZ