

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-30203-00-00 ^{01 KCC}
Spot: CE2 Sec/Twnshp/Rge: 25-34S-15W
2640 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: DAVIS RANCH T Well Number: 1
County: BARBER Total Vertical Depth: 4890 feet

Operator License No.: 6769 Conductor Pipe: Size 13.375 feet: 199
Op Name: WESTMORE DRILLING COMPANY, INC. Surface Casing: Size 8.625 feet: 931 WITH 100 SX CMT
Address: 1614 CYPRESS POINT DRIVE Production: Size 4.5 feet: 4889 WITH 75 SX CMT
LAWRENCE, KS 66047 11/16 Liner: Size feet: 158.93

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/08/2001 10:15 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: HERB DURANT Company: WESTMORE DRILLING Phone: (785) 749-3712

Proposed Plugging Method: PUMP 200 SX HULLS & 25 SX CMT. GEL SPACER 900'-0'. 1ST PLUG AT 4300' WITH 15 SX GEL & 25 SX CMT WITH HULLS. CIRCULATE CMT FROM 900' TO SURFACE. PUMP 150 SX CMT DOWN 13 3/8 X 8 5/8" ANNULUS.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 01/16/2001 11:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:
PBTD 4620'. PERFS AT 4324-28'. CIBP @ 4620'. ON 12/28/00 CASING LEAK SQUEEZED AT 490' WITH 200 SX CMT. CMT CIRCULATED OUT 4 1/2 X 8 5/8 ANNULUS. 1ST PLUG SPOT PLUG THROUGH TUBING INSIDE 4 1/2" CASING WITH 15 SX GEL & 25 SX CMT AT 4308'. MIX HULLS THROUGHOUT BOTTOM PLUG. 2ND PLUG CIRCULATE INSIDE 4 1/2" CASING THROUGH 2 3/8" TUBING. CIRCULATE CMT FROM 900' TO SURFACE WITH 63 SX CMT. 1/15/01 FILLED 8 5/8 X 4 1/2" ANNULUS WITH 25 SX CMT. (TAG CMT @ 130'.) PUMPED 285 SX CMT AND 500# HULLS DOWN 8 5/8 X 13 3/8" ANNULUS. COULD NOT LOAD HOLE. SDON. 1/16/01 PUMPED 75 SX CMT AND 200# HULLS. MAXIMUM PRESSURE 375#. SHUT IN @ 0#. WAIT ON CMT FOR 1 HR. TESTED TO 50# AND HELD.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
Plugged through: TBG

District: 01 Signed: Steve Pfeifer (TECHNICIAN)
INVOICED
DATE 1/22/01 JAN 19 2001 JAN 16 2001 Form CP-2/3
INV. NO. 2001061352 CONSERVATION DIVISION