

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20234-00-02
Spot: NWNE Sec/Twnshp/Rge: 10-30S-34W
4645 feet from S Section Line, 1986 feet from E Section Line
Lease Name: LEATHERS LAND Well #: 3-10
County: HASKELL Total Vertical Depth: 5700 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4100		WITH 2 SX CMT
CIBP		5270		
SURF	8.625	1816		WITH 950 SX CMT
PROD	5.5	5694	2334	WITH 325 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/13/2012 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STEVE EMICH Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 4100' WITH 2 SX CMT. PLUG AT 1850' WITH 20 SX GEL & 50 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/13/2012 2:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

WELL CURRENTLY HAS CIBP SET @ 5270'. SET CIBP @ 4100' WITH 2 SX CMT. 1ST PLUG RIH W/TBG TO 1850' & PUMPED 20 SX GEL & 50 SX CMT. 2ND PLUG PUMPED 50 SX CMT AT 630'. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4580	4590		KANSAS CITY A
4168	4178		LANSING B

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL.

Plugged through: TBG

District: 01

RECEIVED
MAR 21 2012
KCC DODGE CITY

Signed Jack MacLaskey
(TECHNICIAN)

RECEIVED
APR 02 2012
KCC WICHITA

Form CP-2/3

4/03/12
RWY