

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-107-24566-00-00  
Spot: NWNESENW Sec/Twnshp/Rge: 31-21S-22E  
3809 feet from S Section Line, 2558 feet from E Section Line  
Lease Name: MITCHELL FAMILY TRUST 31 Well #: 31-1  
County: LINN Total Vertical Depth: 822 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	21		8 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/23/2012 10:00 AM  
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC  
Proposal Rcvd. from: SHIRLEY STOTLER Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: CEMENT PLUGS AT TD, 500 FEET, AND FROM 250 FEET TO SURFACE.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE  
Date/Time Plugging Completed: 03/02/2012 11:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TO 822 FEET THEN PUMP GEL TO SURFACE. PLACE 100 FOOT CEMENT PLUG AT 820 FEET, ANOTHER 100 FOOT CEMENT PLUG AT 500 FEET, AND FILL TO SURFACE WITH CEMENT FROM 250 FEET. USE TOTAL OF 130 SACKS OF CEMENT.

RECEIVED  
MAR 28 2012 LS  
KCC Chanute Dist. #3

Perfs:

Remarks:  
Plugged through: TBG

District: 03

Signed L. Short  
(TECHNICIAN)

RECEIVED Form CP-2/3  
APR 02 2012 4/03/12  
KCC WICHITA