

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-093-20381-00-00  
Spot: NWSE Sec/Twnshp/Rge: 8-24S-36W  
1979 feet from S Section Line, 2044 feet from E Section Line  
Lease Name: LOUCKS B GU Well #: 2  
County: KEARNY Total Vertical Depth: 3031 feet

Operator License No.: 32446  
Op Name: MERIT ENERGY COMPANY, LLC  
Address: 13727 NOEL RD STE 500  
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	735		WITH 350 SX CMT
PROD	5.5	3029	0	WITH 700 SX CMT

Well Type: GAS UIC Docket No: Date/Time to Plug: 03/13/2012 2:00 PM

Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.

Proposal Rcvd. from: Company: Phone:

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/14/2012 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TBG STUCK IN HOLE. SQUEEZE PERFS WITH 50 SX CMT WITH HULLS. SDON.  
3/14/12: TEST SQUEEZE TO 500#. HOLDING. SHOT TBG OFF AT 1992'. PULL TO 1955'. PUMP 50 SX CMT CLASS C CEMENT & 2% CC W/HULLS AT 1955'. FULL CIRCULATION. TOOH W/TBG. STRETCH TEST. PULL 50,000# ON THE 5 1/2" CASING. HAD 1" OF STRETCH. TOC CALCULATED AT 200' FROM SURFACE. RUN TBG TO 750'. FILL 5 1/2" FROM 750' TO 0' WITH 80 SX CMT. FILL ANNULUS WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2784	2786		PANOMA COUNCI

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED

MAR 21 2012

KCC DODGE CITY

RECEIVED

APR 02 2012

KCC WICHITA

Form CP-2/3

4/03/12

