

1050315

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,017-00-00

C NW NE, SEC. 31, T 16 S, R 27 W/EX  
4620 FSL feet from ~~XXXX~~ section line  
1980 FEL feet from ~~XXXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9726

Lease Name Becker Well # 1

Operator: Gruss Petroleum Management, Inc.  
Name & Address: 900 Building of the Southwest  
Midland, TX 79701

County Lane

Well Total Depth 4650 151.13 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 385

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor DNB Drilling License Number 5476

Address 535 North Oliver, Box 8292-C, Wichita, KS 67208

Company to plug at: Hour: 1:00 pm Day: 10 Month: August Year: 1984

Plugging proposal received from Jack Taylor

(company name) DNB (phone) 316-687-5471

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2170' with 50 sx cement

2nd plug at 1110' with 70 sx cement

3rd plug at 420' with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 3:30 pm Day: 10 Month: August Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 2170' with 50 sx cement, 2nd plug at 1110' with 70  
sx cement, 3rd plug at 420' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -  
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with  
15 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-7-84

INV. NO. 3575

STATE CORPORATION COMMISSION

SEP 04 1984

CONSERVATION DIVISION  
Wichita, Kansas

Signed Richard W. Lacey  
(TECHNICIAN)