

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-01696-00-00  
Spot: NWSESESE Sec/Twnshp/Rge: 28-17S-8W  
524 feet from S Section Line, 422 feet from E Section Line  
Lease Name: FULLER OO Well #: 5  
County: ELLSWORTH Total Vertical Depth: 3229 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	206		175 SX
L1	4.5	3291		50 SXS
PROD	6	3178		300 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/16/2012 10:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: MARK ROBBEN Company: MURFIN DRILLING Phone: (785) 735-4621

Proposed Plugging Method: SEE BELOW. 4.5" LINER SET AT 3151-3320' WITH 50 SX'S CEMENT. THIS WELL HAS HAD OTHER PERFS THAN WHAT IS LISTED SQUEEZED OFF.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/20/2012 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS AND ATTEMPTED TO PULL TUBING. TUBING WAS STUCK-AFTER USING HYDRAULIC JARS TO FREE UP--WAS ABLE TO GET IT OUT. TAGGED TD AT 3165' WITH SAND PUMP. FOUND NUMEROUS CASING LEAKS BETWEEN 360-390', 830-1162', & 2095-2126'. PERFORATE AT 1200', 800', AND 260'. RUN TUBING TO 3160' AND PUMP 60 SX'S COMMON CEMENT WITH 3% CC. PULL TUBING TO 1200' AND PUMP 50 SX'S COMMON CEMENT - 3% CC WITH COTTON HULLS. PULL TUBING TO 800' AND PUMP 50 SX'S COMMON CEMENT - 3% CC WITH COTTON HULLS. PULL TUBING OUT AND LET SET FOR 1 HR. ATTEMPTED TO TAG CEMENT--COULD NOT. SHUT DOWN FOR DAY, AFTER USING 160 SX'S. CAME BACK ON 3-20-12, RAN TUBING DOWN AND STACKED OUT AT APPROX. 540'. PULLED TUBING UP TO 430' AND CIRCUALTED CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. CONNECTED ON TO SURFACE CASING AND PUMPED CEMENT--PRESSURED UP TO 300#'S AND SHUT IN. USED 110 SX'S ON 3-20-12.

Perfs:

Top	Bot	Thru	Comments
3258	3268	CSG	
3178	3228	CSG	
3170	3186	CSG	
3044	3050	CSG	
2923	2929	CSG	
2900	2904	CSG	
2886	2890	CSG	
2840	2850	CSG	

RECEIVED  
MAR 29 2012  
KCC WICHITA

Remarks: PERF TECH TICKET #9170. QUALITY WELL CEMENT #475 ON 3-16-12. QUALITY TICKET #261 ON 3-20-12.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

4/05/12