

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-21499-00-01  
Spot: SENWSW Sec/Twnshp/Rge: 25-24S-33W  
1396 feet from S Section Line, 4030 feet from E Section Line  
Lease Name: KANSAS B Well #: 6-25  
County: FINNEY Total Vertical Depth: 3045 feet

Operator License No.: 32864  
Op Name: XTO ENERGY INC.  
Address: 210 PARK AVE STE 2350  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2501		
CIBP		2811		WITH 10 SX CMT
SURF	8.625	485		WITH 225 SX CMT
PROD	5.5	3045	0	WITH 600 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/09/2012 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: SAUL Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 2510'. CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/09/2012 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2501'. CIRCULATE CMT FROM 2470' TO 0' IN TWO STAGES USING A TOTAL OF 230 SX CMT. TOOH W/TBG & TOP OFF WITH 20 SX CMT. PUMP 5 SX CMT DOWN THE ANNULUS.

Perfs:


Top	Bot	Thru	Comments
2851	2891		COUNCIL GROVE
2612	2618		WINFIELD
2560	2574		HERRINGTON

Remarks: USED CLASS C CEMENT & 2% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_



(TECHNICIAN)

RECEIVED

MAR 22 2012

KCC DODGE CITY



RECEIVED

APR 02 2012

KCC WICHITA

Form CP-2/3

4/05/12

