

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21712-00-017
Spot: S2NWSWSW Sec/Twnshp/Rge: 9-32S-34W
797 feet from S Section Line, 340 feet from W Section Line
Lease Name: DOWNING A Well #: 3
County: SEWARD Total Vertical Depth: 6274 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5700		WITH 2 SX CMT
CIBP		6050		
SURF	8.625	1726		WITH 435 SX CMT
DVT		3025		WITH 310 SX CMT
PROD	5.5	6270	0	WITH 120 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/13/2012 9:30 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KENNY ANDREWS Company: OXY USA Phone: (713) 215-7000

Proposed Plugging Method: SET CIBP @ 5700' WITH 2 SX CMT. RIH W/TBG TO 1750' & PUMP 30 SX CMT. TAG TOC & PULL STRETCH ON 5 1/2" CASING TO ATTEMPT TO RECOVER MINIMUM 5/0' OF 5 1/2" CASING. PUMP 40 SX CMT AT 580' & 12 SX CMT AT 40'.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL
Date/Time Plugging Completed: 03/13/2012 5:00 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

SET CIBP @ 5700' WITH 2 SX CMT. RIH W/TBG TO 1750' & PUMPED 30 SX CMT. SDON. TAGGED TOC @ 2700'. RIH W/TBG TO 1750' & PUMPED 30 SX CMT WITH GOOD CIRCULATION. CMT NEVER FELL. UNABLE TO GET CASING SLIPS OUT OF CASING HEAD. NO STRETCH ON 5 1/2" CASING. PUMPED 30 SX CMT AT 580'. PUMP 5 SX CMT AT 50'. TIED ONTO 8 5/8" X 5 1/2" ANNULUS. UNABLE TO PUMP INTO. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
6175	6196		
6158	6167		
6112	6152		
5750	5760		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: TBG

District: 01

RECEIVED

MAR 21 2012

KCC DODGE CITY

Signed

Jack MacClaskey
(TECHNICIAN)

RECEIVED

APR 02 2012

KCC WICHITA

Form CP-2/3

RAW 2