

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20863-00-00
Spot: SWSWSENW Sec/Twnshp/Rge: 4-16S-32W
2650 feet from S Section Line, 1413 feet from W Section Line
Lease Name: HOEME Well #: 1-4
County: SCOTT Total Vertical Depth: 4780 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	220		WITH 165 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/23/2012 8:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: TONY MARTIN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 2400' WITH 50 SX CMT. 2ND PLUG AT 1800' WITH 80 SX CMT. 3RD PLUG AT 900' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: NONE
Date/Time Plugging Completed: 03/23/2012 11:15 PM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

Perfs:

1ST PLUG AT 2400' WITH 50 SX CMT. 2ND PLUG AT 1800' WITH 80 SX CMT. 3RD PLUG AT 900' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONOSOLIDATED.

Plugged through: DP

District: 01

RECEIVED
MAR 30 2012
KCC DODGE CITY

Signed Daniel Bernasconi
(TECHNICIAN)

RECEIVED
APR 02 2012
KCC WICHITA
Form CP-2/3
4/05/12
RANZ