

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-20230-00-00
Spot: SENENW Sec/Twnshp/Rge: 36-22S-9E
990 feet from N Section Line, 2310 feet from W Section Line
Lease Name: BIG SPRINGS A B C Well #: B-1
County: CHASE Total Vertical Depth: 2636 feet

Operator License No.: 6534
Op Name: SCHINDLER, ROBERT DBA SCHINDLE
Address: RR 1 PO BOX 92
MADISON, KS 66860

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	65		30 SXS CMT
PROD	4.5	2630	1247	75 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/12/2011 8:00 AM
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC
Proposal Rcvd. from: ROBERT SCHINDLER Company: _____ Phone: (620) 437-2525

Proposed Plugging Method: PLUG BACK 10' ABOVE TOP PERF AND CAP W/5 SX. RIP AND PULLED 250' OF 4 1/2" CASING, SET BRIDGE AT 250', AND CEMENT TO SURFACE.

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 09/12/2011 8:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

Perfs:

TUBING WAS STUCK IN HOLE BUT WAS CIRCULATED LOOSE. DROPPED SAND WITH WATER TO TD (2636') AND DUMP BAILER CAPPED WITH 6 SX OF 60 X 40 4% GEL. TAGGED PLUG @ 2480. RIPPED CASING AND RECOVERED 1247'. BRIDGE WAS SET AT 267' AND TUBING WAS THEN RAN TO 260'. CONSOLIDATED PUMPED 115 SX OF CEMENT TO SURFACE.


RECEIVED
APR 03 2012
KCC WICHITA

Remarks: CONSOLIDATED TICKET #31587.

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

Form CP-2/3

4/05/12

JK