

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-20409-00-00
Spot: SWSENW Sec/Twnshp/Rge: 36-22S-9E
2310 feet from N Section Line, 1650 feet from W Section Line
Lease Name: BIG SPRINGS A B C Well #: B-2
County: CHASE Total Vertical Depth: 2612 feet

Operator License No.: 6534
Op Name: SCHINDLER, ROBERT DBA SCHINDLE
Address: RR 1 PO BOX 92
MADISON, KS 66860

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	153		100 SXS CMT
T1	2.375	2610	1600	
PROD	4.5	2612	574	100 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/17/2011 8:00 AM
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC
Proposal Rcvd. from: ROBERT SCHINDLER Company: _____ Phone: (620) 437-2525

Proposed Plugging Method: PLUG BACK 10' ABOVE TOP PERF AND CAP W/5 SX. RIP AND PULLED 250' OF 4 1/2" CASING, SET BRIDGE AT 250', AND CEMENT TO SURFACE.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 09/06/2011 8:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report: _____ Perfs: _____


TUBING WAS STUCK IN HOLE AND COULD NOT BE WASHED OUT (TUBING WAS CONFIRM TO BE RAN ALL THE WAY TO BOTTOM). CONSOLIDATED PUMPED 50 SX OF 60 X 40 4% GEL DOWN TUBING TO TD. TUBING WAS THEN SHOT OFF @ 1600' AND PULLED. 10 SX WERE THEN DUMP BAILED ON TOP OF SHOT TUBING. CASING WAS RIPPED AND 574' WERE RECOVERED. BRIDGE WAS SET AT 252' AND CEMENTED TO SURFACE. CONSOLIDATED TICKET #31550 (BOTTOM PLUG) CONSOLIDATED TICKET #31425 (TOP PLUG)

Remarks: PLUGGING WAS NOT WITNESSED DUE TO SCHEDULING CONFLICTS.

Plugged through: TBG

District: 02

Signed _____



(TECHNICIAN)

RECEIVED

APR 03 2012 CP-2/3

KCC WICHITA

✓