

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-30064-00-02
Spot: NESWNE Sec/Twnshp/Rge: 25-22S-9E
1650 feet from N Section Line, 1650 feet from E Section Line
Lease Name: BIG SPRINGS A B & C Well #: WS-1
County: CHASE Total Vertical Depth: 1665 feet

Operator License No.: 6534
Op Name: SCHINDLER, ROBERT DBA SCHINDLE
Address: RR 1 PO BOX 92
MADISON, KS 66860

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1570		
SURF	7	1664		100 SX
COND	9	301		250 SX
PROD	4.5	1400		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2011 8:00 AM
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC
Proposal Rcvd. from: ROBERT SCHINDLER Company: _____ Phone: (620) 437-2525

Proposed Plugging Method: PLUG BACK 10' ABOVE TOP PERF AND CAP W/5SX. RIP AND PULLED 250' OF 4 1/2" CASING, SET BRIDGE AT 250', AND CEMENT TO SURFACE.

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2011 8:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

WELL WAS WASHED DOWN TO 1538' AND STACKED OUT, BAILER WAS BRINGING UP VERY HEAVY MUD/OILY SLUDGE. RAN IN 2 3/8 TUBING AND PUMPED 60 SX OF 60X40 4% GEL AND PULLED TUBING. PLUG WAS TAGGED AT 920'. CASING WAS CEMENTED IN TOP TO BOTTOM SO NO PERFORATION WAS REQUIRED. BRIDGE WAS SET AT 250' AND CEMENTED TO SURFACE. CONSOLIDATED TICKET #31608.

Perfs:


Top	Bot	Thru	Comments
1400	1664	OH	OPEN HOLE

Remarks: THIS WAS AN OLD WATER SUPPLY WELL THAT WAS CONVERTED TO A DISPOSAL THEN BACK TO A WATER SUPPLY WELL. CASING WAS CEMENTED IN TO SURFACE.

Plugged through: TBG

District: 02

Signed _____



(TECHNICIAN) RECEIVED

APR 03 2012

Form CP-2/3

KCC WICHITA