

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-101-20232-00-00

API NUMBER N/A

LEASE NAME Johnson

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 8 TWP. 17 RGE. 27W (S) or (W)

COUNTY Lane

Date Well Completed

Plugging Commenced 8-27-92

Plugging Completed 8-28-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS P.O. Box 56 RT #1 Great Bend, Kansas 67530

PHONE# (316) 793-8166 OPERATORS LICENSE NO. 5393

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 4565'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	242'	none
				4 1/2"	4544'	785'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 4100', ran 4 sacks cement. Shot pipe @1300' pumped 50 sacks,
shot pipe @800' pumped 50 sacks pulled rest of pipe loaded surface with 50 sacks.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A. L. Abercrombie, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 1 day of Sept., 19 92

My Commission Expires:

IRENE HERZBERG
State of Kansas
My Appt. Exp. Aug. 24, 1993

Form CP-4
Revised 05-88

RECEIVED
STATE CORPORATION COMMISSION
SEP 2 1992
CONSERVATION DIVISION
Wichita, Kansas

DESIGNATE TYPE OF COMP. OIL, GAS, DRY HOLE, SWD, ETC. Oil

Operator
Abercrombie Drilling, Inc.

Well No. 1 Lease Name JOHNSON

s. 8 T. 17S. R. 27^W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay & sand	0	40	SAMPLE TOPS:	
Rock	40	70		
Shale & sand	70	200	Anhydrite	2062 (+577)
Shale	200	250	B/Anhydrite	2107 (+532)
Sand	250	1420	Heebner	3884 (-1245)
Shale	1420	1600	Toronto	3903 (-1264)
Sand	1600	1815	Lansing	3922 (-1283)
Shale & sand	1815	1960	Stark Shale	4172 (-1532)
Shale	1960	2062	B/KC	4240 (-1601)
Anhydrite	2062	2107	ELECTRIC LOG TOPS:	
Shale	2107	2580		
Shale & lime	2580	3365	Anhydrite	2050 (+589)
Lime & shale	3365	3538	B/Anhydrite	2082 (+557)
Shale & Lime	3538	3824	Heebner	3880 (-1241)
Lime & shale	3824	4032	Toronto	3903 (-1264)
Lime	4032	4539	Lansing	3922 (-1283)
Shale & lime	4539	4565	Stark Shale	4172 (-1533)
Rotary Total Depth		4565	B/KC	4242 (-1603)
DST #1 (4103-4136) 30", 45", 60", 45". Weak steady blow. Rec 120' soc muddy water. IFP 22-32, IBHP 1205, FFP 54-65, FBHP 1195. Temp. 122.				
DST#2 (4139-4176) 30", 45", 60", 45". Fair blow. Rec. 180' gip, 60' clean oil - 37°, 60' ocm, 60' mw. IFP 76-76, IBHP 465, FFP 108-119, FBHP 444. Temp. 124				
DST#3 (4179-4193) 30", 45", 60", 45". Good blow. Rec. 1140' gip, 302' clean gassy oil, 38°, 60' ocm with salt saturated water. IFP 54-65, IBHP 809, FFP 108-151, FBHP 744. Temp 124				
DST#4 (4403-4445) 30", 45", 60", 45". Fair blow. Rec. 90' gip, 30' mo-80% oil. IFP 43-54, IBHP 433, FFP 54-54, FBHP 173. Temp. 127.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Jack L. Partridge
Signature

Jack L. Partridge, Assistant Secretary-Treasurer

February 10, 1978
Date

3007 5 106