

15-101-20365-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Lane _____ County. Sec. 8 Twp. 17 Rge. 27 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
SE SE SE

Lease Owner Oxford Exploration Co., Inc.
Lease Name Pfeifer Well No. 1
Office Address 1030 Denver Club Bldg., Denver, Colo. 80202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed 2/8/79 19
Application for plugging filed 2/8/79 19
Application for plugging approved 2/8/79 19
Plugging commenced 2/8/79 19
Plugging completed 2/8/79 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____
Show depth and thickness of all water, oil and gas formations. TD 4660'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	366'	8-5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug at 850' with 70 sacks 50/50 Poz, 6% gel
Middle plug at 300' with 20 sacks 50/50 Poz, 6% gel
Top and bridge at 40' with 10 sacks 50/50 Poz, 6% gel
5 sacks in rathole
Job complete 1 a.m. 2/8/79

RECEIVED
STATE CORPORATION COMMISSION
FEB 21 1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Slawson Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick
James C. Remsberg (employee of owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg
James C. Remsberg
200 Douglas Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of February, 1979

Mary Lou Taylor
Mary Lou Taylor Notary Public.

My commission expires January 17, 1981



15-101-20365-00-00

DRILLERS LOG

OPERATOR: Oxford Exploration Company, Inc.
 1030 Denver Club Building
 Denver, Colorado 80202

LEASE: Pfeifer No. 1
 SE SE SE Sec. 8-17S-27W
 Lane County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
 200 Douglas Building
 Wichita, Kansas 67202

COMMENCED: 1/31/79

COMPLETED: 2/8/79

RTD: 4660

CASING: 8-5/8" set at 366' with 250 sx cement

0' to 270' Clay & Sand with post rock at 60'
 270' to 370' Shale (370' 12 1/4" Surface Hole)
 370' to 550' Shale & Shells
 550' to 1300' Shale & Sand
 1300' to 1360' Lime & Shale
 1360' to 1675' Shale
 1675' to 1885' Sand
 1885' to 1930' Shale
 1930' to 2144' Shale with sand stks.
 2144' to 2174' Anhydrite
 2174' to 2445' Shale & Shells
 2445' to 2627' Shale & Sand
 2627' to 2910' Shale & Lime
 2910' to 3980' Lime & Shale
 3980' to 4620' Lime & Shale
 4620' to 4660' Lime & Shale
 RTD 4660'

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 21 1979
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg of the Slawson Drilling Company, Inc.
 hereby state the above is an accurate copy of the Pfeifer No. 1 log for
 Oxford Exploration Company, Inc.

James C. Remsberg
 James C. Remsberg

Subscribed and sworn to me this 19th day of February, 1979

Mary Lou Taylor
 Mary Lou Taylor, Notary

My commission expires January 17, 1981

