


15-101-20077-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Layne County. Sec. 7 Twp. 17 Rge. 27W E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines \_\_\_\_\_  
SE SW SW  
Lease Owner O.A. Sutton  
Lease Name Hanks Well No. 1  
Office Address 800 Sutton Place Wichita Ks  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above.  
Section Plot

Oil  
Date Well completed 10/ 1975  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 12/27 1976  
Plugging completed 12/29 1976  
Reason for abandonment of well or producing formation \_\_\_\_\_  
Dry  
If a producing well is abandoned, date of last production \_\_\_\_\_  
12/1 1976

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation Miss Depth to top 4612 Bottom 4616 Total Depth of Well 4700  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	333	8 5/8		
		0	4699	4 1/2		135

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug set at 4510 filled with sand to 4440 and dumped 3 sx cement

Pumped with Halliburton in 8 5/8 casing 70 sx 6 % jell 50-50 poz, 5 sx. jell 1 sx hulls and 70 sx. 50-50 poz cement complete w/200#

RECEIVED  
STATE CORPORATION COMMISSION

JAN 11 1977

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Nicholas Casing Pulling  
Wichita, Kansas

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.  
(employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) George B. Nicholas

(Address)

SUBSCRIBED AND SWORN TO before me this 10<sup>th</sup> day of January, 1977

Julia A. Waggoner  
Notary Public.

My commission expires April 29, 1980



GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

15-101-20077-00-00

HANKS #1  
SE SW SW, Sec. 7-17S-27W  
Lane County, Kansas

COMMENCED: November 19, 1973  
COMPLETED: December 2, 1973

OPERATOR: O. A. Sutton

Depth		Formation	Remarks
From	To		
0	345	Surface Soil-Sand-Shale	Ran 8 jts. of used 8 5/8" csg. set @341' cemented w/225 sks. common cement, 2% Gel, 3% CC. P.D. @7:15 AM - 11-19-73. Cement circ. Job by Halliburton.
345	680	Shale	
680	1330	Shale-Sand	
1330	1577	Shale	Ran 143 jts. of used 4 1/2" csg. set @4699' cemented w/175 sks. 50/50 Posmix, Salt Sat. P.D. @10:45 PM - 12-2-73. Job by Halliburton.
1577	1589	Blaine Anhydrite	
1589	1650	Shale	
1650	1880	Sand	
1880	2075	Shale-Redbed	RECEIVED STATE CORPORATION COMMISSION  JAN 10 1977  CONSERVATION DIVISION Wichita, Kansas
2075	2140	Redbed	
2140	2180	Anhydrite	
2180	2232	Shale	
2232	2490	Shale-Redbed	
2490	2663	Shale	
2663	3960	Lime-Shale	
3960	4545	Lime	
4545	4600	Lime-Chert	
4600	4635	Sand-Shale	
4635	4700	Sand-Shale-Chert	

4700 T.D.

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled in the SE SW SW, Sec. 7-17S-27W, Lane County, Kansas to the best of my knowledge and belief.

*James S. Sutton II*  
JAMES S. SUTTON II

STATE OF KANSAS )  
                              ) SS  
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 4th day of December, 1973, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

*Marjorie Hall*  
MARJORIE HALL - NOTARY PUBLIC



My Commission Expires: November 29th, 1975.