

SIDE TWO

Operator Name Slawson Exploration Co., Inc. Lease Name RAMSEY 'Z' Well # 2

Sec. 30 Twp. 17S Rge. 30 East West
County Lane

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken Yes No
(Attach Additional Sheets.)
Samples Sent to Geological Survey Yes No
Cores Taken Yes No
Electric Log Run Yes No
(Submit Copy.)

"See Attached Copy"

Formation Description

Log Sample

Name Top Bottom

"See Attached Copy"

CASING RECORD

New Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface		8-5/8	25#	374	60/40 Poz	200	2% gel, 3% CC

PERFORATION RECORD

Acid, Fracture, Shot, Cement Squeeze Record
(Amount and Kind of Material Used) Depth


Shots Per Foot	Specify Footage of Each Interval Perforated	

TUBING RECORD Size Set At Packer At Liner Run Yes No

Date of First Production Producing Method Flowing Pumping Gas Lift Other (Explain)

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity

Disposition of Gas: Vented Sold Used on Lease (If vented, submit ACO-18.) **METHOD OF COMPLETION** Open Hole Perforation Dually Completed Commingled Other (Specify) _____



- HELD CONFIDENTIAL -
ORIGINAL

ATTACHMENT SHEET for
Ramsey 'Z' #2
Sec. 30-17S-30W
Lane County, Kansas
API #101-21,595-00-00

RELEASED
AUG 7
SEP 14 1993 CONFIDENTIAL

FROM CONFIDENTIAL

DST #1 - 3957'-3985' (LKC 35' zone) Weak blow on 1st open, dead on 2nd open, times 30-45-20-20 min; rec 20' sli OCM, (7% oil, 93% mud). IFP 34-34#, FFP 38-38#, ISIP 994#, FSIP 756#.

DST #2 - 4257-4272' (Middle Creek) 1st weak blow died 11", rec 1' DM.

DST #3 - 4345-4380' (Alta 'B') 1st blow 6" BLW, 3" BLO, times 30-45-45-60 min, rec 2' FO, 90' OSWM, 210' SW. IFP 51-74#, FFP 100-156#, ISIP 1004#, FSIP 998#.

DST #4 - 4382'-4490' (Altamont 'C', Ft Scott, Pawnee) times 30-45-45-60, rec 5' FO, 70 vsli OCM. IFP 23-29#, FFP 35-39#, ISIP 911#, FSIP 801#, HP 2078-2065#, BHT 116°F.

SAMPLE TOP:

Anhydrite	2267' (+639')	Stark	4215' (-1309')
B. Anhydrite	2287' (+619')	BKC	4300' (-1394')
Wabaunsee	3514' (-608')	Alt 'B'	4371' (-1465')
Topeka	3665' (-759')	Pawnee	4420' (-1514')
Heebner	3900' (-994')	Miss	4552' (-1646')
Lansing	3940' (-1034')	RTD	4605'
35' zone	3974' (-1068')		

LOG TOP:

Anhydrite	2265' (+641')	BKC	4297' (-1391')
B. Anhydrite	2285' (+621')	Alta 'B'	4367' (-1461')
Wabaunsee	3511' (-605')	Pawnee	4415' (-1509')
Topeka	3662' (-756')	Ft. Scott	4462' (-1556')
Heebner	3897' (-991')	Lw Cher	4483' (-1577')
Lansing	3937' (-1031')	Johnson	4624' (-1618')
35' zone	3971' (-1065')	Sand	4540' (-1634')
Stark	4211' (-1305')	Miss	4549' (-1643')

Strap at TD 1.61 short to board.

RECEIVED
STATE COMMISSION

AUG 29 1991

DIVISION
Wichita, Kansas

Phone 913-483-2627, Russell, Kansas
 Phone 316-793-5861, Great Bend, Kansas

Phone Plainville 913-434-2812
 Phone Ness City 913-798-3843

RELEASED ORIGINAL

SEP 14 1993

ALLIED CEMENTING CO., INC.

Home Office P. O. Box 31

FROM CONFIDENTIAL Russell, Kansas 67665

No. 1450
 KCC

AUG 27

New

Date <u>8-6-91</u>	Sec. <u>30</u>	Twp. <u>17</u>	Range <u>30</u>	Called Out <u>12:30 P.M.</u>	On Location <u>2:30 P.M.</u>	Job Start <u>4:10 P.M.</u>	Finish <u>7:00 P.M.</u>
Lease <u>Ranscy 2</u>		Well No. <u>2</u>		Location <u>Manning 2E</u>		County <u>Lane</u>	State <u>Ks</u>
Contractor <u>Abricrombie R.T.D. Rig #5</u>				Owner <u>Stinson Exploration Company, INC.</u>			
Type Job <u>P. Plug</u>				To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.			
Hole Size <u>7 7/8</u>		T.D. <u>4605</u>		Charge To <u>Stinson Exploration Company, INC.</u>			
Csg.		Depth		Street <u>20 N. Broadway Suite 700</u>			
Tbg. Size		Depth		City <u>Okla. City</u> State <u>Okla.</u> <u>73102</u>			
Drill Pipe <u>4 1/2</u>		Depth <u>2300</u>		The above was done to satisfaction and supervision of owner agent or contractor.			
Tool		Depth		Purchase Order No.			
Cement Left in Csg.		Shoe Joint		X <u>Neil Washle</u>			
Press Max.		Minimum		CEMENT			
Meas Line		Displace		Amount Ordered <u>215 69/106 709 1470 Flo Seal</u>			
Perf.				Consisting of			

EQUIPMENT

No.	Cementer	
Pumptrk	Helper	
Pumptrk <u>#158</u>	Cementer	<u>J.D.</u>
	Helper	<u>Bob</u>
	Driver	<u>Mike</u>
Bulktrk <u>#109</u>		
Bulktrk	Driver	

Common	<u>129</u>	<u>5.25</u>	<u>677.25</u>
Poz. Mix	<u>86</u>	<u>2.25</u>	<u>193.50</u>
Gel.	<u>13</u>	<u>6.75</u>	<u>87.75</u>
Chloride			
Quickset			
	<u>Flo Seal 54 #</u>	<u>1.00</u>	<u>54.00</u>
		<u>Sales Tax</u>	
Handling	<u>215</u>	<u>1.00</u>	<u>215.00</u>
Mileage	<u>50</u>		<u>430.00</u>
		<u>Sub-Total</u>	
		<u>Total</u>	<u>1657.50</u>

DEPTH of Job

Reference:	<u>Pump Truck Charges</u>	<u>475.00</u>
<u>50</u>	<u>Mileage</u>	<u>100.00</u>
<u>18 1/2 O.H.P.</u>		<u>20.00</u>
	<u>Sub-Total</u>	
	<u>Tax</u>	
	<u>Total</u>	<u>595.00</u>

Floating Equipment

<u>Total \$</u>	<u>2252.50</u>
<u>Disc -</u>	<u>337.88</u>
	<u>\$ 1914.62</u>

Remarks:
50 ex 2300 10 ex M.H.
50 ex 1450 15 ex R.H.
30 ex 750 By Allied Cementing
50 ex 400 Thank you
10 ex 40 Fred Warner

RECEIVED STATE CORPORATION COMMISSION

AUG 29 1991

CONSERVATION
 Wichita, Kansas