

State of Kansas



15-101-19014-00-00 FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Bob Boyd of Helmerich & Payne, Inc., has this
date requested permission to plug the following described well:

Mr. Boyd guarantees payment of the plugging fee.

Operator's full Name: Helmerich & Payne, Incorporated,

Complete Address: Box # 558, Garden City, Kansas.

Lease Name: Leighton Well No. A-1

Location: CSE-NE Sec. 9 Twp. 17 Rge. (E) (W) 27

County Lane Total Depth 4547 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Boyd was instructed to plug the well as follows:

285'--8 5/8" Surface pipe, cement circulated w/200 SX.

Circulate hole with heavy mud, set plug @ 660' and 20 Sx cement.

"	"	280' with $\frac{1}{4}$ Sk hulls & 20 Sx cement.
"	"	40' with $\frac{1}{2}$ Sk hulls & 10 Sx. cement.

Very truly yours,

H. L. Nichols
Conservation Division Agent