



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION

JAN 23 1974

CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Wilmer Dreiling of Gabbert-Jones, Incorporated, has this date requested permission to plug the following described well:

Mr. Dreiling guarantees payment of the plugging fee.

Operator's full Name: O. A. Sutton,

Complete Address: 800 Sutton Place, Wichita, Kansas.

Lease Name: Hanks Well No. 2

Location: NE-SW-NW Sec. 7 Twp. 17 Rge. (E)(W) 27

County: Lane Total Depth 4620' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Dreiling was instructed to plug the well as follows:

359'--8 5/8" Surface casing, cement circulated with 235 Sx. Top of Dakota section @ 750'.

Circulate hole with heavy mud. Pull DP to 975' and displace 110 Cu. Ft. cement thru DP. Pull DP to 375' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

[Handwritten Signature]

Conservation Division Agent