

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 6 1971
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Iannitti of Woodman - Iannitti Drlg. has this date requested permission to plug the following described well:

Mr. Iannitti guarantees payment of the plugging fee.

Operator's full Name: Thornton E. Anderson

Complete Address: 710 Union Natl. Bldg., Wichita, Ks.

Lease Name: Lamer-Elmore Well No. 1

Location: S/2 NE SW Sec. 26 Twp. 17 Rge. (E)(W) 22

County: Ness Total Depth 4290' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Iannitti was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 550' and displace
70 sk cmt thru drill pipe. Heavy mud to 215' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

[Signature]
 Conservation Division Agent