

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 30 1977

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock --
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Moore of C & G Drlg. has this
date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Liberty Enterprises, Inc.

Complete Address: 308 W. Mill, Plainville, Ks.

Lease Name: Majors Well No. 1

Location: C NW SW Sec 14 Twp. 17 Rge. (E)(W) 22

County: Ness Total Depth 4324' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Moore was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 660' thru drill

pipe. Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Geo Messing
Conservation Division Agent

7121