

State of Kansas



15-093-30060-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 23 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bishop of Leben Drilling Inc. has this

date requested permission to plug the following described well:

Mr. Bishop guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling Incorporated

Complete Address: 815 Wichita Plaza, Wichita, Kansas

Lease Name: Hullman Well No. 1

Location: C NW NW Sec 29 Twp. 21 Rge. 35 (E)(W)

County Kearny Total Depth 4700' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bishop was instructed to plug the well as follows:

8 5/8" to 403' Circulated w/ cement . T.D. 4700' 7 7/8" Hole

Mud 4700' to 450' Spotted 35 sax cement 450' to 350'

Mud 350' to 45' Plug, hulls & 15 sax cement 45' to 0

Haliburton Pump Truck

Very truly yours,

Edgar J. Eves
Conservation Division Agent