

State of Kansas



15-093-30064-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 14 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bishop of Shallow Water Refin. Co. has this  
date requested permission to plug the following described well:

Mr. Bishop guarantees payment of the plugging fee.

Operator's full Name: Shallow Water Refining Co.

Complete Address: 1325 Wichita Plaza, Wichita, Kansas

Lease Name: Beissel Well No. 1

Location: C NE SW Sec. 17 Twp. 21 Rge. 35 (E) (W)

County Kearny Total Depth 5146' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Bishop was instructed to plug the well as follows:

8 5/8" to 418' circulated w/ cement, T.D. 5146'  
Mud 5146' to 660' Spotted 25 sacks cement 660' to 585'  
Mud 585' to 400' Spotted 20 sacks cement 400' to 340'  
Mud 340' to 40' Plug, Hulls & 10 sacks cement 40' to 0'

Very truly yours,

Edmund J. Eves  
Conservation Division Agent