



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 9 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Claude Norwood of DNB Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: DNB Drilling, Incorporated,

Complete Address: 701 First National Building, Wichita, Kansas.

Lease Name: Conkright Well No. C-2

Location: CNW-NE-NW Sec. 27 Twp. 16 Rge. (E)(W) 25

County: Ness Total Depth 4528' Oil Well \_\_\_\_\_

Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X Lost Hole \_\_\_\_\_

Mr. Norwood was instructed to plug the well as follows:

300'--8 5/8" Surface casing, cement circulated with 225 Sx.

Circulate hole with heavy mud. Pull DP to 750' and displace 50 Sx. cement thru DP. Pull DP to 250' and displace 25 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx cement to bottom of cellar.

Very truly yours,

*A. L. Nichols*

Conservation Division Agent