



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Burris of Chief Drlg. Co., Inc. has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drlg. Co., Inc.

Complete Address: Box 797 Great Bend, Ks.

Lease Name: Conkright Well No. 1

Location: SW NW Sec. 27 Twp. 16 Rge. 25 (E)(W) X

County: Ness Total Depth 4520' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 900' and displace
70 sc cmt thru drill pipe. Heavy mud to 300' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with
2 sc cement.

RECEIVED
STATE CORPORATION COMMISSION
Very truly yours,

OCT 1 - 1968

CONSERVATION DIVISION
Wichita, Kansas

[Signature]
Conservation Division Agent