

15-101-20012-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Lane _____ County. Sec. 2 Twp. 17 Rge. 27W (E) _____ (W)

Location as "NE/CNW/SW" or footage from lines NW NE NE

Lease Owner Thunderbird Drilling, Inc.

Lease Name Hagans 'H' Well No. 1

Office Address Box 18407, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 8 19 71

Application for plugging filed July 8 19 71

Application for plugging approved July 8 19 71


Plugging commenced July 8 19 71

Plugging completed July 8 19 71

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Bill Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4580 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	320'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 925', 100 sacks cement

Mud to 340', 25 sacks cement

Mud to 40', plug, 1/2 sack hulls, 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Don Gardner (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) [Signature]

Suite 250, 200 West Douglas, Wichita, Kansas
(Address)

Subscribed and Sworn to before me this 9th day of July, 19 71

My commission expires December 14, 1973

[Signature]
Notary Public.



15-101-20012-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1971
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

#1 HAGANS "H"
NW NE NE Section 2-17-27W
Lane County, Kansas

OPERATOR: Thunderbird Drilling, Inc.
P. O. Box 18407
Wichita, Kansas

CONTRACTOR: Dunne-Gardner Petroleum, Inc.
Suite 250, 200 West Douglas
Wichita, Kansas

COMMENCED: June 25, 1971

COMPLETED: July 8, 1971

CASING RECORD: 8-5/8" @ 320' w/225 sx

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	40	Surface clay and sand
40	320	Shale and sand
320	900	Shale
900	992	Sand
992	1225	Shale and lime streaks
1225	1465	Shale and shells
1465	1475	Anhydrite
1475	2034	Shale
2034	2075	Anhydrite
2075	2245	Shale
2245	2567	Shale and lime
2567	3405	Lime and shale
3405	4580	Lime
4580		Rotary Total Depth

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

DUNNE-GARDNER PETROLEUM, INC.


Don Gardner

Subscribed and sworn to before me this 9th day of July, 1971.

My commission expires:
December 14, 1973


Notary Public

