

15-101-20009-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Affidavit to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Lane _____ County, Sec. 1 Twp. 17 Rge. 27 (X) (W)
Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner Thunderbird Drilling, Inc.
Lease Name Hagans "J" Well No. 1
Office Address 4328 East Kellogg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 29, 19 71
Application for plugging filed April 29, 19 71
Application for plugging approved April 29, 19 71
Plugging commenced April 29, 19 71
Plugging completed April 29, 19 71
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4545 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		0	281	8-5/8	4/17/71	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed; from _____ feet to _____ feet for each plug set.

Fill hole with heavy mud to 720' from surface and pump 70 sacks cement. Mud to 270' from surface and 20 sacks cement. Mud to 40' from surface, set plug, 1/4 sack hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Don Gardner (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Suite 250, 200 West Douglas, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of April, 19 71
My commission expires March 1, 1974
Dorothy M. Mikish
Notary Public.



15-101-20009-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 1 1971
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

#1 HAGANS "J"
NE NE SE Section 1-17S-27W
Lane County, Kansas

OPERATOR: Thunderbird Drilling, Inc.
4328 East Kellogg
Wichita, Kansas

CONTRACTOR: Dunne-Gardner Petroleum, Inc.
Suite 250, 200 West Douglas
Wichita, Kansas

COMMENCED: April 17, 1971

COMPLETED: April 29, 1971

CASING RECORD: 8-5/8" @ 281' w/225 sx

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	281	Clay and blue shale
281	1086	Shale
1086	1420	Shells & shale
1420	1430	Anhydrite
1430	1495	Shale
1495	1700	Sand
1700	1998	Shale and lime streaks
1998	2030	Anhydrite
2030	2302	Shale
2302	2950	Lime and shale
2950	3350	Lime
3350	3550	Lime and shale
3550	4545	Lime
4545		Rotary Total Depth

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)


I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

DUNNE-GARDNER PETROLEUM, INC.


Don Gardner

Subscribed and sworn to before me this 5th day of May, 1971.

My Commission expires:
December 14, 1973


Notary Public