


15-101-20011-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Lane _____ County, Sec. 1 Twp. 17 Rge. 27W (E) _____ (W)
Location as "NE/CNW/SW" or footage from lines SE NW NE
Lease Owner Thunderbird Drilling, Inc.
Lease Name Hagans "G" Well No. 2
Office Address 4328 East Kellogg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed _____ May 13 19 71
Application for plugging filed _____ May 13 19 71
Application for plugging approved _____ May 13 19 71
Plugging commenced _____ May 13 19 71
Plugging completed _____ May 13 19 71
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4588 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	290'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 950', 70 sacks cement
Mud to 310', 20 sacks cement
Mud to 40', plug, 1/4 sack hulls, 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet).

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Don Gardner (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____
Suite 250, 200 West Douglas, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of May, 19 71
December 14, 1973
My commission expires _____

Notary Public.

15-101-20011-00-00

DRILLERS LOG

#2 HAGANS "G"
SE NW NE Section 1-17-27W
Lane County, Kansas

OPERATOR: Thunderbird Drilling, Inc.
4328 East Kellogg
Wichita, Kansas

CONTRACTOR: Dunne-Gardner Petroleum, Inc.
Suite 250, 200 West Douglas
Wichita, Kansas

COMMENCED: April 30, 1971

COMPLETED: May 13, 1971

CASING RECORD: 8-5/8" @ 290' w/225 sx

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	280	Clay, blue shale
280	840	Shale
840	950	Sand
950	1435	Shale and shells
1435	1451	Anhydrite
1451	1570	Shale
1570	1767	Sand
1767	1775	Shale
1775	2020	Shale and shells
2020	2059	Anhydrite
2059	2125	Shale
2125	2910	Lime and shale
2910	3180	Lime
3180	3985	Lime and shale
3985	4588	Lime
4588		Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1971
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

DUNNE-GARDNER PETROLEUM, INC.


Don Gardner

Subscribed and sworn to before me this 14th day of May, 1971.

My commission expires:
December 14, 1973


Notary Public