

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,005-00-00

LEASE NAME Munsell

WELL NUMBER #1

SPOT LOCATION 990' FNL & 940' FEL

SEC. 6 TWP. 17 RGE. 27 (E) of (W)

COUNTY Lane

Date Well Completed 8-12-84

Plugging Commenced 8-12-84

Plugging Completed 8-12-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR White & Ellis Drilling, Inc.

ADDRESS 401 E. Douglas, Suite 500, Wichita, KS 67202

PHONE # (316) 263-1102 OPERATORS LICENSE NO. 5420

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1

Is ACO-1 filed? NO If not, is well log attached? Yes

Producing formation N/A Depth to top _____ bottom _____ T.D. 4600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	389'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Spotted 50 sx cement @ 2130' thru drill pipe.

Spotted 50 sx cement @ 840' thru drill pipe.

Spotted 50 sx cement @ 420' thru drill pipe.

Spotted 10 sx cement @ 40' thru drill pipe.

Spotted 15 sx cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420
Address 401 East Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.


STATE CORPORATION COMMISSION

(Signature) Ernest Sifford


(Address) 401 E. Douglas, Suite 500
Wichita, Ks. 67202

AUG 31 1984

My Commission expires: _____ before me this 30th day of August, 1984



David F. Jamis
Notary Public



15-101-21005-00-00

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

White & Ellis Drilling, Inc.
 OPERATOR: 401 E. Douglas, Suite 500
 Wichita, KS 67202
 CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
 Wichita, Ks. 67202

Lease Name Munsell Well No. #1
 Sec. 6 T. 17S R. 27W Spot 990' FNL & 940' FEL
 County Lane State Kansas Elevation _____

Casing Record:

Surface: 8 5/8 @ 389' with 200 sx. 2% gel
3% cc

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4600'

Drilling Commenced 8-5-84 Drilling Completed 8-13-84

Formation	From	To	Tops
Cellar	0	7	Anhydrite - 2105
Shale	7	802	
Shale, Lime	802	2070	
Shale	2070	2104	
Shale, Lime	2104	4170	
Lime, Shale	4170	4600	