

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-101-00077-0000

API NUMBER N/A

LEASE NAME Leighton

WELL NUMBER A-1

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 4 TWP. 17 RGE. 27 (E) or (W)

COUNTY Lane

Date Well Completed 3-20-64

Plugging Commenced 5-15-91

Plugging Completed 5-15-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS P.O. Box 558 Garden City, Kansas

PHONE#(316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well Oil - TA'd.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-13-91 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed?            If not, is well log attached? Yes

Producing Formation LKC Depth to Top 4029 Bottom 4193 T.D. 4241

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil & Water	4060	64	8 5/8	330	0
"	" "	4040	47	4 1/2	4275	0
"	" "	4029	33			
"	" "	4120	28			
"	" "	4186	93			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from          feet to          feet each set  
Pump 50 bfw ahead. Pump 30 sks 60/40 poz. 6% gel w/100# bulls. Displace w/55 bbls gel, 1/2 BPM  
@ 500# w/cmt. on bottom ISIP - 450#. Perforate 4 holes @ 1250'. Wait 3 hours. Pump 150 sks  
60/40 poz 6% gel at 2 BPM at 750# to 200# increasing to 400# down 4 1/2" csg. Pump 150 sks 60/40  
poz 6% gel down 4 1/2 x 8 5/8 annulus at 200 to 500#.

(If additional description is necessary, use BACK of this form.)

Top plug. 0 to 1250'. Bottom plug 3600 to 4100

Name of Plugging Contractor Halliburton License No.                     

Address Ness City, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Helmerich & Payne, Inc.

MAY 20 1991

STATE OF Kansas COUNTY OF Finney, ss.


CONSERVATION DIVISION  
Wichita, Kansas

Ken Jehlik (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Ken Jehlik

(Address) P.O. Box 558 Garden City, Ks.



SUBSCRIBED AND SWORN TO before me this 16th day of May, 19 91

Judy S. Richmeier  
Notary Public

My Commission Expires: August 15, 1992