

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-101-20485-00-00

LEASE NAME Kuehn

RECEIVED

JAN 10 2003

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 2

330 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 4 TWP. 17 RGE. 27 (E) or (W)

COUNTY Lane

LEASE OPERATOR Abercrombie Energy, LLC

ADDRESS Rt. #1, Box 56 Great Bend, Ks. 67530

PHONE# (620) 793-8186 OPERATORS LICENSE NO. 32457

Date Well Completed 1-2-81

Plugging Commenced 1-7-03

Plugging Completed 1-7-03

Character of Well \_\_\_\_\_

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-6-03 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? Don't Know If not, is well log attached? No

Producing Formation Lansing KC Depth to Top 4148 Bottom 4180 T.D. 4480

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing KC	Oil-Water	4148	54	8 5/8	307	None
		4174	80	4 1/2	4295	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Top fish (tbq. left in hole) 2122'. Bottom plug 2089' with 18 Bbl. Gel, 55 sacks common w/3% cc & 150# hulls. WOC 1 1/2 hrs. Press bottom plug 500#. Perf 2 holes @ 1200'. Displace 155 sacks 60/40 Poz 6% gel. Shut in w/700# PSI. Hook up to annulus - displace 65 sacks 60/40 Poz 6% gel down 8 5/8 casing. Shut in with 600# PSI.

Name of Plugging Contractor Abercrombie Energy, LLC License No. 32457

Address Rt. #1, Box 56 Great Bend, Ks. 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie Energy, LLC

STATE OF Kansas COUNTY OF Barton, ss.

E. L. Abercrombie (Employee of Operator) or (Operator) or above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) E L Abercrombie

(Address) Rt. #1, Box 56 Great Bend, Ks. 67530



SUBSCRIBED AND SWORN TO before me this 8th day of January, 2003

Susan M. Urban  
Notary Public

My Commission Expires: 7-29-2004

OR